Port House

WMH 2+ / 33 60 m2





WENDI MODULAR SIA

Reģistrācijas Nr. 44103126151 Adrese: Kungu iela 7, Cēsis, LV - 4101

e-pasts: info@wendimodular.lv

Modular House




Room PLAN







Construction elements



Facade:

Roof– Profile Classic 50 Plus matt RR33 0,50mm, matt black Facade boards– Wooden board (dried, KD16%) 120x22, finely sawn, painted (tone by choice)

Interior:

Flooring: vinyl laminate or parquet in living rooms, stone tiles in WC room. Walls/ceiling: Wooden boards 120 x 12mm, painted (white lasur), tiles in shower section

Communications:

Electro installation, sockets, switches (Schneider Sedna Pro, color- graphite)

Junction box Schneider/ABB

Sewerage and water connection points

Water heater Electrolux EWH 50I (or analogue)

Sink with cabinet + faucet

Shower floor drain

Shower System Hansgrohe Ecostat 1001 CL (or analogue)

Built-in wall WC system Grohe + toilet bowl with soft-close rim

Ventilation in WC room S&P Silent Design D100

WC room- Electrical heated floor system DEVI with termoregulator DeviReg Smart (with wi-fi)

Windows & Doors:

Entrance doors, windows-PVC, 3 glass packet 36mm,

Average U-value- 0,96 W/m2k.

Interior doors: Veneered solid wood doors or painted wooden doors with visible wood texture Internal wooden (ash tree) window sills

Exterior window sills- sheet metal, tone matched to the color of the roof

Additional services by request (not included in offer price)

House transportation and installation costs
Preparation of foundation
Furniture set (kitchen with appliances, closet, stairs to loft)- 6000 eur

Price – 84000 Eur EXW

*Any visual or other changes in project by request